



Park Hill School District

Building Successful Futures • Each Student • Every Day

REQUEST FOR PROPOSAL

2018 Floor Refinishing

Congress Middle School

Lakeview Middle School

Plaza Middle School

Park Hill High School

Park Hill South High School

Detailed Proposal Information is Available on District Website

<http://www.parkhill.k12.mo.us>

Bid Closing Date: March 8, 2018

Bid Closing Time: 10:00 am CST

Park Hill School District reserves the right to reject any or all proposals and to waive informalities or irregularities in any proposal.



Park Hill School District

Building Successful Futures • Each Student • Every Day

February 26, 2018

Dear Contractor:

The Park Hill School District (DISTRICT) is seeking proposals from qualified contractors (CONTRACTOR) for wood floor refinishing at various schools in the Park Hill School District.

Bids are to be returned to Jim Rich, Park Hill School District, 8500 NW River Park Drive, Pillar 116, Parkville, MO 64152. All bids are to be returned before 10:00 a.m., March 8, 2018. The bid sheet may be emailed to RichJ@parkhill.k12.mo.us or faxed to 816-359-4109. Please mark your bid "Bid Proposal-Floor Refinishing". Your bid amount will be placed on the enclosed specification sheet and must be signed by an authorized representative of your dealership.

Please call 816-359-4100 to schedule a time if you need to look at the gyms.

If your company has not done work in the Park Hill School District in the past three school years, please provide a school client contact list including phone numbers and contact names.

The DISTRICT reserves the right to reject any and all proposals and to waive informalities.

Sincerely,

A handwritten signature in black ink that reads "Jim Rich".

Jim Rich
Director of Operations



Park Hill School District

Building Successful Futures • Each Student • Every Day

General Notes

1. DISTRICT will remove all tape, gum, equipment, etc. from the hardwood floor surface.
2. CONTRACTOR will screen-back the full gym floor area using a high-speed buffer and 120 grit screens.
3. CONTRACTOR will tack the floor with treated tack towel to remove all dirt and residue.
4. CONTRACTOR will apply one liberal coat of Hillyard 450 Gymnasium Finish or equivalent MFMA approved, oil modified urethane gym finish to the floor. This coat of finish will provide a uniform coverage with no dull spots or lap marks.

